



Test Report: RSD-100B-5

100W Single Output DC-DC Converter

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

DESIGN VERIFY TEST
OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 100 mVp-p (Max)	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	V1 : 92 mVp-p (Max)	P
2	OUTPUT VOLTAGE TOLERANCE	V1 : 2%~ -2% (Max)	I/P : 14.4 VDC / 33.6VDC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0.4 %~ -0.4 %	P
3	LINE REGULATION	V1 : 0.5%~ -0.5% (Max)	I/P : 14.4VDC ~ 33.6VDC O/P : FULL LOAD Ta : 25°C	V1 : 0.12 %~ -0.12 %	P
4	LOAD REGULATION	V1 : 1%~ -1% (Max)	I/P : 24VDC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0.4 %~ -0.4 %	P
5	SET UP TIME	24VDC : 800 ms (Max)	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	24VDC/ 222 ms	P
6	RISE TIME	24VDC : 50 ms (Max)	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	24VDC/ 3.9 ms	P
7	HOLD UP TIME	24VDC : 3 ms (Typ.)	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	24VDC/ 3.9 ms	P
8	OVER/UNDERSHOOT TEST	< ±5%	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	TEST : <5 %	P
9	DYNAMIC LOAD	V1 : 1000 mVp-p	I/P : 24VDC (1).O/P : FULL /Min LOAD 90%DUTY/ 1KHZ (2).O/P : FULL /Min LOAD 50%DUTY/ 120HZ Ta : 25°C	(1)412 mVp-p (2)498 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	14.4VDC~33.6VDC	I/P : TESTING O/P : FULL LOAD Ta : 25°C	12.5 VDC~33.6VDC	P
			I/P : LOW-LINE-14.2V HIGH-LINE=35.28 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN (DC POWER ON/OFF NO DAMAGE)	TEST : OK	
2	EFFICIENCY	88 % (TYP)	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	88.49 %	P
3	INPUT CURRENT	24VDC/ 4.8 A (TYP)	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	I = 4.71 A/ 24VDC	P
4	INRUSH CURRENT	24VDC/ 30 A (TYP) COLD START	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	I = 14 A/ 24VDC	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105 % ~ 135 %	I/P : 24VDC O/P : TESTING Ta : 25°C	121 %/ 24VDC Constant Current Limiting	P
2	OVER VOLTAGE PROTECTION	CH1 : 5.75 V ~ 7 V	I/P : 24VDC O/P : MIN LOAD Ta : 25°C	6.694 V/ 24VDC Shut down Re- power on to recover	P
3	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 33.6VDC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Constant Current Limiting recover automatically after fault condition is removed	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q 2 Rated : IRFB3607PBF 80A/75V	I/P : High-Line +3V =36.6V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 54.4 V (2) 58 V (3) 46 V	P
2	Diode Peak Voltage	Q104 Rated : STP85N3LH5 80A/30V	I/P : High-Line +3V = 36.6V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 29.4 V (2) 28 V (3) 29 V	P
3	Input Capacitor Voltage	C5 Rated : 470u/50V L10Kh 12.5*20 YXG	I/P : High-Line +3V = 36.6V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 32.808 V (2) 33.458 V (3) 33.469 V	P
4	Control IC Voltage Test	U 1 Rated : PWM LM5026MT 7.3V~16V	I/P : High-Line +3V = 36.6V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 14.556 V (2) 14.642 V (3) 14.552 V	P

SAFETY & E.M.C. TEST
SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 4 KVDC/min I/P-FG : 2.5 KVDC/min O/P-FG : 2.5 KVDC/min	I/P-O/P : 4.4 KVDC/min I/P-FG : 3 KVDC/min O/P-FG : 3 KVDC/min Ta : 25°C	I/P-O/P : 0.002 mA I/P-FG : 0.002 mA O/P-FG : 0.002 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C /70%RH	I/P-O/P : 29.1 GΩ I/P-FG : 25.7 GΩ O/P-FG : 24.6 GΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta : 25°C / 70%RH	14 mΩ	P
4	APPROVAL	TUV : Certificate NO : UL : File NO :			N/A

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RADIATION	EN55022 CLASS B	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
2	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR : 8KV / Contact : 4KV	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
3	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT : 0.5KV	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
4	SURGE	IEC61000-4-5 MEDICAL LIGHT INDUSTRY L-N : 0.5KV L,N-PE : 0.5KV	I/P : 24VDC O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	Test by certified Lab & Test Report Prepare				

RELIABILITY TEST
ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : RSD-100B-5 1. ROOM AMBIENT BURN-IN : 2 HRS I/P : 24VDC O/P : FULL LOAD Ta=28.7℃ ℃ 2. HIGH AMBIENT BURN-IN : 16 HRS I/P : 24VDC O/P : FULL LOAD Ta=50.9℃ ℃			P
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P : 24VDC O/P : 118 % LOAD Ta : 25℃	TEST : OK	P
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 33.6VDC/14.4VDC O/P : 100 % LOAD Ta= -40 ℃	TEST : OK	P
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 55 ℃ NO DAMAGE	I/P : 33.6 VDC O/P : FULL LOAD Ta= 55℃ HUMIDITY= 95 %R.H	TEST : OK	P
5	TEMPERATURE COEFFICIENT	± 0.03 % (0~50℃)	I/P : 24VDC O/P : FULL LOAD	± 0.009 % (0~50℃)	P
6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45℃~ +90℃ 2. Temperature change rate : 25℃ / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	P

7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -45°C~ +60°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 24VDC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec	OK	P
8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 5G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
9	CAPACITOR LIFE CYCLE	RSD-100B-5:SUPPOSE C105 IS THE MOST CRITICAL COMPONENT (1) I/P : 24VDC O/P : FULL LOAD Ta= 25 °C LIFE TIME (2) I/P : 24VDC O/P : FULL LOAD Ta= 55 °C LIFE TIME (3) I/P : 24VDC O/P : 75% LOAD Ta= 55 °C LIFE TIME (4) I/P : 24VDC O/P : 50% LOAD Ta= 55 °C LIFE TIME	(1) 95232HRS (2) 13920HRS (3) 39456HRS (4) 95904HRS	P
10	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 254.1K HRS		P
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 30,000 hours @ TA 55°C		P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2011/2/9	RD SAMPLE	PASS	SANFORD SU	VINCENT TSENG
2011/4/6	PRODUCT SAMPLE W1103D13	PASS	SANFORD SU	VINCENT TSENG

2009/08/04 A50-F023